BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Modified Schedule - B

NAME OF WORK:		Desilting and Restting of Drain and Reasphalting to MEI Layout new Extn main road and cross roads in ward No 14 bagalagunte.			
Sl No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1(a) / 2.3.1 (P.No.6 l.No.2.3)with all lead and lift charges & as per direction of engineer incharge of work.	Cum	478.11	193.19	Rupees One Hundred Ninety Three and Nineteen Paise Only
2	Providing and laying in position plain cement concrete of mix1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machinery, curing complete as per specifications. (P.13/4.3)with all lead and lift charges & as per direction of engineer incharge of work.	Cum	65.14	5506.55	Rupees Five Thousand Five Hundred Six and Fifty Five Paise Only
3	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No. 17 / Item No.4.36)with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	1065.96	386.39	Rupees Three Hundred Eighty Six and Thirty Nine Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Sl No.	Description of work	Unit	Qty	Approved Rate	
				In Figures (Rs.)	In Words
4	Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs. with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to is 9103 1999 reafirmed 2008, machine mixed concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6with all lead and lift charges & as per direction of engineer incharge of work.	Cum	132.93	6107.71	Rupees Six Thousand One Hundred Seven and Seventy One Paise Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (TMT bars FC 500)(P.18/4.46.2) Issue rate date : 02.11.2021 till now with all lead and lift charges & as per direction of engineer incharge of work.	Tonnes	7.98	94348.47	Rupees Ninety Four Thousand Three Hundred Forty Eight and Forty Seven Paise Only
6	Providing and and fixing Precast Concrete slab 10 CM thick with all lead and lift as per specification (Data Rate Approved) 2018-19with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	340.09	2379.53	Rupees Two Thousand Three Hundred Seventy Nine and Fifty Three Paise Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
7	Transportation & disposing off the excavated earth obtained from side drains and high burns an either side of the road 2 km lead with all lead and lift charges & as per direction of engineer incharge of work.	Cum	486.30	87.21	Rupees Eighty Seven and Twenty One Paise Only
E-1	Removing and Resetting of Footpath slab(Approved data Rate)with all lead and lift charges & as per direction of engineer incharge of work.	Sqm	165.24	231.69	Rupees Two Hundred Thirty One and Sixty Nine Paise Only
E-2	Dismantling cement Concrete manually by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer incharge (P-163/I-19.2.11)with all lead and lift charges & as per direction of engineer incharge of work.	Cum	8.19	1381.64	Rupees One Thousand Three Hundred Eighty One and Sixty Four Paise Only

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division